

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

6-13-82 RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1982

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)
15-175-20,631

Dear Sir:

Mr. John Hanna of Anadarko Production Co. has this date requested permission to plug the following described well:

Operator's Full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal Kansas 67901

Lease Name: Crow Well No. B2

Location: C-SW-NE-SW Sec. 26 Twp. 33 Rge. 34 (E) (W)

County: Seward Total Depth: 6490'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Hanna was instructed to plug the well as follows:

They set 1657' of 8 1/8" surface casing cement circulated. 1st plug at 2600' with 40 sbx of cement. 2nd plug at 1680' with 40 sbx of cement. 3rd plug at 820' with 35 sbx of cement. 4th plug at 40' to 0' with 10 sbx of cement on solid bridge. Then circulated 10 sbx cement in rat hole + 10 sbx in mouse hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Halliburton Co.
Very truly yours,

Paul A. Luttich
Conservation Division Agent