

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 16 1967

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 20 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Duncan of Ashland Oil & Refining has this date requested permission to plug the following described well:

Mr. Duncan guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining

Complete Address: 720 N. W. 50th St., Oklahoma City, Oklahoma

Lease Name: Theis Well No. 1

Location: NW 38 Sec. 6 Twp. 35 Rge. 25 (E) (W)

County Clark Total Depth 6215' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Duncan was instructed to plug the well as follows:

8 5/8" to 514' circulated w/ cement. 4 1/2" to 6142' cemented.

Plug bottom w/ 15 sacks cement. Top of cement 6080'

Mud 6080' to 550' Spotted 35 sacks cement 550' to 450'

Mud 450' to 40' Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Edgar J. Eves
Conservation Division Agent