

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 25 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Mallonee-Coppinger Oper. has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Coppinger Operations Incorporated

Complete Address: 1207 Union National Building, Wichita, Kansas

Lease Name: Keating Well No. 1

Location: SW SW Sec. 33 Twp. 34 Rge. 34 (EX) (W)

County Seward Total Depth 6650' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1366' circulated w/ cement. \$ 4 1/2" to 4488' cemented.

Top perforations 4380' Plug bottom w/ 20 sacks cement.

Top of cement 4200' Mud 4200' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Hulls & 15 sacks cement 45' to 0. Company Pump.

Very truly yours,

Edgar J. Eves
Conservation Division Agent