

KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 84 4 Location: CNE 1/2

County: Meade Sec. 5 Twp. 34S Rge 26W (E) (W) W

Name of Field or Pool: _____ Total Depth: 5941

I have this date completed supervision of plugging of:

Well No. 1 Lease Ediger

Operator's Full Name Tennessee Gas Transmission Co.

Complete Address: Box 163, Great Bend, Kans.

Plugging Contractor: West Supply

Address: Chase, Kans. License No. 14

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour 3P.M. Day 28 Month February Year 1958

The above well was plugged as follows:

8 5/8" sUrface 1400' circulated with cement. Hole was sanded to 5742'.
Perf were 5757-65. 5 sack cement was dumped with dump bailer on top
of sand to 5704'. Hole was filled with heavy dell mud to 560' with a
rock bridge set. 20 sack cement on rock bridge from 488 to 435'. Mud
to 25' with rock bridge and 10 sack cement to sUrface.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed:
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

STATE CORPORATION COMMISSION

MAR 8 1958

Reviewed:
Field Supervisor

Signed: _____
Well Plugging Supervisor

CONSERVATION DIVISION
Kansas

Remarks:

PLUGGING
REC 5 T 3YR 264
BOOK PAGE 84 LINE 7