

RECEIVED
STATE CORPORATION COMMISSION

KANSAS

FORM CP-3
Rev. 1-8-82

JUN 22 1982

STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION AGENT REPORT

API Number 15-119-20564

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Gulf Oil Exploration & Production Co.

Complete Address P.O. Box 12116, Oklahoma City, Okla. 73157

Lease Name Theis Well No. C-21

Location 2160' FSL-330' FWL Sec. 7 Twp. 34 Rge. 26 (East)(West)

County Meade Total Depth 6000'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Raines & Williams Oil Co. Inc.

Address 435 Page Court, 220 West Douglas Wichita, KS 67202 License No. _____

Operation Completed: Hour: 7:30 AM Day: 20 Month: June Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

1st plug at 1320' with 60 lbs of cement. 2nd plug at 300' with 50 lbs of cement. 3rd plug at 40' to 0' with 10 lbs of cement. Then circulated 10 lbs of cement in each the rat hole & mouse hole. The cement used was 50/50 Pos with 4% gel & 3% CC. The cement was pumped through the drill pipe with the hole full of heavy mud. The plugging was accomplished by Halliburton Co. Mr. Morrison Schmidt gave these orders while I was seeing another well plugged

Amount of Surface Casing: 1302' of 8 5/8" cement circulated

I hereby certify that the ⁵⁰⁰ above plugging instructions were given as herein stated.

Signed: Paul A. Luthis
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED

DATE 6-28-82

INV. NO. 499-W