

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 - 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma City, Oklahoma

Lease Name Berends Well No. 1

Location App C SW/4 Sec. 31 Twp. 34 Rge. 25 (NE) (W)

County Clark Total Depth 6200'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Gayle E. Toland

Address: Oklahoma City, Oklahoma, Box 94336 License No. 539

Operation Completed: Hour 3:00PM Day 30 Month 1 Year 1968

The Above well was plugged as follows:

8 5/8" to 709' circulated w/ cement. 4 1/2" to 6200' cemented.

Top perforations 5818' Plug bottom w/ 15 sacks cement.

Top of cement 5750' Mud 5750' to 750'

Spotted 35 sacks cement 750' to 650' Mud 650' to 40'

Plug. Halls & 10 sacks cement 45' to 0' Company Pump

Pulled 5003' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICE

Signed: 
Well Plugging Supervisor

DATE 2/6/68
INV. NO. 7211-W