

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Imperial Oil of Kansas Inc.
Complete Address: 780 Fourth National Bldg., Wichita, Kansas
Lease Name Meredith Well No. # 1
Location C NW SE Sec. 28 Twp. 34 Rge. 28 (E) (W) W
County Meade Total Depth 3325
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:

Plugging Contractor: Chemical & Technical Service Inc.
Address: Box D, Hill City, Kansas License No.
Operation Completed: Hour 3:45PM Day 1st Month Jan. Year 1965

The Above well was plugged as follows:
1350' of 7" surface pipe, cement circulated with 450 sacks. Hole was
filled with drilling mud, and 35 sacks of cement was spotted at 700',
through the drill pipe. Hole was filled with drilling mud to 45',
bridge plug set on fluid at 45', and cemented with 15 sacks to the
base of the cellar.
This cementing was done by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1-6-65
INV. NO. 484-W

Signed: Archie Elving
Well Plugging Supervisor