

1060244

15-175-20302-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,302

C NW SW, SEC. 15, T. 33 S, R. 31 W/X

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6230

Lease Name Headrick Well # 1-15

Operator: First National Oil, Inc.

County Seward

Name & Address 23 East 11th, Park Plaza

Well Total Depth 5985 194.5' feet

Liberal, KS 67901

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1593

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 3:00 pm Day: 1 Month: June Year: 19 84

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2 set at 2753' Perfs 2597-2612 PBD 2753'

RECEIVED
STATE CORPORATION COMMISSION

1st plug pump 25 sx cement and 1 sack hulls on the bottom

2nd plug at 1643' with 50 sx cement

3rd plug at 750' with 30 sx cement
solid bridge

JUN 05 1984

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Paul A. Luthie
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 5:00 pm Day: 1 Month: June Year: 1984

ACTUAL PLUGGING REPORT 5 1/2 set at 2753' Perfs 2597-2612' PBD 2753'

1st plug pumped 25 sx cement and 1 sack hulls on the bottom, 2nd plug at 1653' with 50

sx cement, 3rd plug at 750' with 30 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement.

Remarks: Used Common sacked cement, recovered 2280' 5 1/2" casing. by Sargent's

(If additional description is necessary, use BACK of this form.)

INVOICED (11/10/84) observe this plugging.

DATE 6-15-84

Signed Paul A. Luthie
(TECHNICIAN)

INV. NO. 2024

6-1