

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21799-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 19-33S-31W  
330 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: DAVIES Well Number: 1-19  
County: SEWARD Total Vertical Depth: 5900 feet

Operator License No.: 8061

Conductor Pipe: Size \_\_\_\_\_ feet:

Operator Name: OIL PRODUCERS, INC. OF KANSA

Surface Casing: Size 8.625

feet: 1596

Address: PO BOX 8647  
WICHITA, KS 67208

Production: Size 4.5

feet: 2768

Liner: Size \_\_\_\_\_

feet: \_\_\_\_\_

191.75

Well Type: GAS

UIC Docket No: \_\_\_\_\_

Date/Time to Plug: 10/06/2000 9:00:00 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Revd. from: RICHARD MCINTYRE

Company: QUALITY WELL SERVICE, INC.

Phone: (316) 278-2476

Proposed Plugging Method: SAND BACK TO 2431' WITH 4 SX CMT BAILED ON TOP. PULL CASING UP TO 1230'. PUMP 12 SX GEL & 50 SX CMT. PULL UP TO 600'. PUMP 50 SX CMT. PULL UP TO 40'. PUMP 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/06/2000 11:00 AM

KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 2491-2584. TOC @ 1362'. SANDED BACK TO 2431' WITH 4 SX CMT BAILED ON TOP. 1ST PLUG PULLED CASING UP TO 1230' & PUMPED 12 SX GEL & 50 SX CMT. 2ND PLUG PULLED UP TO 600' & PUMPED 50 SX CMT. 3RD PLUG PULLED UP TO 40' & PUMPED 10 SX CMT. WELL WAS CIRCULATING TO SURFACE THROUGHOUT JOB WHEN PUMPING PLUGS.

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 1342' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

INVOICED

Signed

Kevin D. Strube

(TECHNICIAN)

DATE 10/13/00

INV. NO. 2001060814

OCT 11 2000

Form CP-2/3

Left

MP