

1031520

TO: STATE CORPORATION COMMISSION

7-9

API NUMBER 15-175-20,222
E/2 NW SW SEC. 19, T 33 S, R 31 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 910 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HAUSER WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY SEWARD 204.10

OPERATOR LICENSE # 6593

WELL TOTAL DEPTH 6280 FEET

OPERATOR: COASTAL OIL & GAS PRODUCTION CSG: SIZE 4 1/2" @ 5903 WITH 160 SX

NAME AND 9 GREENWAY PLAZA #2751 SURFACE CASING: SIZE 8 5/8" @ 1418' WITH 800 SX

ADDRESS HOUSTON, TX 77046

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING LICENSE NUMBER 31151

ADDRESS ROUTE 1, BOX 49BA TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 8:45 AM DAY: 09 MONTH: 07 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON (PHONE) 580-854-6515

WERE: PERFS AT 5486-5494, 5696-5708, 5718-5730, 5814-5842

1ST PLUG PUMP 20 SX CEMENT AND 500# HULLS AT 5790'. 2ND PLUG AT 3000' WITH 25 SX CEMENT.

3RD PLUG AT 1440' WITH 50 SX CEMENT. 4TH PLUG AT 600' WITH 30 SX CEMENT. 5TH PLUG AT

40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 09 MONTH: 07 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG PUMP 20 SX CEMENT AND 500# HULLS AT 5790'.

2ND PLUG AT 2500' WITH 25 SX CEMENT.

3RD PLUG AT 1440' WITH 50 SX CEMENT.

4TH PLUG AT 600' WITH 30 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED HEAVY MUD BETWEEN ALL PLUGS AND COMMON CEMENT BY SARGENTS.

RECOVERD 2500' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE JUL 19 1999

SIGNED Steve Dumart (TECHNICIAN) FORM CP-2/3

INV. NO. 60045

RECEIVED STATE CORPORATION COMMISSION

JUL 13 1999

CONSERVATION DIVISION Wichita, Kansas

2