

15-175-10079-0000

1 050715

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 12-4-61

C SE NE, SEC. 22, T 33 S, R 31 W/EX

3300 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6230

Lease Name McVey Well # 1

Operator: First National Oil  
Name & Address: 23 East 11th  
Liberal, KS 67901

County Seward 196.95  
Well Total Depth 6060 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1246

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 7:00 am Day: 9 Month: December Year: 19 85

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 6005' Perfs at 5572-80'; 5602-08' Pump through 4 1/2" with mud between plugs

Pump 20 sx cement at 5608'

2nd plug pump 40 sx cement at 1270'

3rd plug pump 30. sx cement at 600'  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:00 am Day: 9 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 25 sx cement to bottom, 2nd plug at 1280' with 50 sx cement, 3rd plug at 660' with 35 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Used common cement by Sargent's Recovered 2170' 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE DEC 18 1985

RECEIVED Signed Richard W. Lacey  
STATE CORPORATION COMMISSION (TECHNICIAN)

INV. NO. 11594

DEC 16 1985