

15-175-10120-0001

R

1 050711

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A

SW NE, SEC. 22, T 33 S, R 31 W/4
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6230

Lease Name McVey Well # 2

Operator: First National Oil, Inc.
Name & Address: 23 East 11th
Liberal, KS 67901

County Seward 96.20
Well Total Depth 2960' feet
Conductor Pipe: Size _____ feet

Surface Casing: Size 13 3/8 feet 600'
Intermediate String 9 5/8" 2482'

Abandoned Oil Well _____ X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 8:00 am Day: 5 Month: December Year: 19 85

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 2960' Perfs at 2601-03'; 2698 1/2-2699'

Pump through 5 1/2" casing with mud between plugs

1st plug pump 1 1/2 sx hulls and 20 sx cement to bottom

2nd plug at 1520' with 50 sx cement

3rd plug at 660' with 50 sx cement

solid bridge - hulls - plug at 40' -- cement to surface

4th plug with 10 sx cement Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:00 am Day: 6 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 1/2 sx hulls and 20 sx cement to bottom, 2nd plug at 1520' with 50 sx cement, 3rd plug at 660' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Recovered 2153' 5 1/2" casing. Used common cement by Sargent's

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE DEC 16 1985

DEC 10 1985

Richard W. Lacey (TECHNICIAN)

INV. NO. 11522

12-6

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 01-84