

To: 1 020487
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-31

15-175-10087-0000
API NUMBER 15- Drilled 1/16/61
NE SW, SEC. 23, T. 33 S, R. 31 W/R
1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Wheatly Well # 2

Operator: A.L. Abercrombie, Inc.

County Seward 195.81

Name:

Address Rt. 1, Box 56

Well Total Depth 6025 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1235

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 31 Month: 7 Year: 19 92

Plugging proposal received from Eddie Abercrombie

(company name) Abercrombie (phone) 316-793-8186

Work: 5 1/2" at 6014' w/125 sx cement, PBSD 5906', Perfs at 4313-18, 4428-30, 5846-96, 5916-22'

1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 175 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 31 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped 3 sx hulls, 5 sx gel, 50 sx cement, 1 sx hulls, 10 sx gel, and 140 sx cement.

Shut in.

Remarks: Used 60/40 Pozmix by Allied. Recovered 2300' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (old / ~~XXXXXX~~) observe this plugging.

DATE 8-10-92

Signed Glenn R Barlow
(TECHNICIAN)

INV. NO. 35902

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1992
CONSERVATION DIVISION
Wichita, Kansas