

1060411

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,405-0000

C SE SW, SEC. 18; T 33 S, R 34 W EX

660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5469

Lease Name Campbell "A" Well # 1

Operator: Anadarko Production Company

County Seward 206.80

Name & Address P. O. Box 351

Well Total Depth 6363 feet

Liberal, KS 67901

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1680

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 2:00 pm Day: 23 Month: November Year: 19 84

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 6317' PBSD 6275' Perfs at 6198-6206'

1st plug pump 1 1/2sacks hulls and 25 sx cement to bottom

2nd plug at 2577' with 40 sx cement

3rd plug at 1654' with 25 sx cement

4th plug at 640' with 20 sx cement
solid bridge -

5th plug hulls - plug at 40' Plugging Proposal Received by Paul A. Luthi
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3:00 pm Day: 23 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 6317' PBSD 6275' Perfs at 6198-6206'

1st plug pumped 1 1/2 sacks hulls and 25 sx cement to bottom, 2nd plug at 2577 with 50 sx

cement, 3rd plug at 1654' with 25 sx cement, 4th plug at 640' with 20 sx cement, 5th &

6th plugs solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement

NOV 28 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 1654' 5 1/2" casing. Used common sacked cement by Sargent's
(if additional description is necessary, use BACK of this form.)

INVOICED (xxx did not) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 12-3-84

INV. NO. 5919 11-23