

7-8

1110150

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-20,126-0000  
C NW SE, SEC. 18, T 33 S, R 34 W/E  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6566  
Operator: Leben Oil Corporation  
Name & Address P.O. Box 21468  
Tulsa, OK 74121-1468

Lease Name McGee Well # 1  
County Seward 160.23  
Well Total Depth 4930 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1686

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Reeves Casing Pulling License Number \_\_\_\_\_  
Address \_\_\_\_\_

Company to plug at: Hour: 12:30 p.m. Day: 7 Month: 7 Year: 19 89

Plugging proposal received from Johnny Gooden

(company name) Reeves Casing Pulling (phone) 405-677-8347

were: 5 1/2" at 4930' PBD 4856' CIBP at 4200 & 4700' Perfs at 4239-42, 4842-49'

1st plug set CIBP at 4300' with 2 sx cement, set CIBP at 4500' with 2 sx cement,

2nd plug pump 30 sx cement at shot joint, 3rd plug pump 50 sx cement at 1725',

4th plug pump 25 sx cement at 800', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 8 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4700' with 15 feet cement,

2nd plug at 2600' with 30 sx cement,

3rd plug at 1720-1620' with 40 sx cement,

4th plug at 800' with 25 sx cement,

5th plug at 40' with 10 sx cement.

Mud between plugs.

Remarks: Recovered 2600' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by B.J. Titan.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 12 1989  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 7-13-89

INV. NO. 25328 7-8 SEP 11 1989

Signed James R. Rankin  
(TECHNICIAN)