

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20327-00-00
Spot: CSESE Sec/Twnshp/Rge: 19-33S-34W
660 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: GUTTRIDGE - A Well Number: 3
County: SEWARD Total Vertical Depth: 6550 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

Production Casing Size: 5.5 feet: 6533 5600 ETOC. \$212.88
Surface Casing Size: 8.625 feet: 1677 CIRCULATED

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/27/2003 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: BOTTOM PLUG 400# HULLS & 25 SX CMT. PLUG AT 1750' WITH 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/27/2003 1:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 6360'. CIBP @ 6360'. PERFS OPEN 6248-53 & 6236-46'. PUMPED DOWN 5 1/2" CASING 400# HULLS & 25 SX CMT. DISPLACED WITH MUD. PRESSURE UP TO 800#. 1ST PLUG PULLED CASING UP TO 1750' & PUMP 50 SX CMT. DISPLACED WITH MUD. 2ND PLUG PULLED UP TO 600' & PUMPED 40 SX CMT. 3RD PLUG PULLED UP TO 40' & PUMPED 10 SX CMT TO SURFACE.

RECEIVED


MAR 14 2003

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2502' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED

DATE 3-14-03

INV. NO. 2003061301

Form 22B