

1 030164

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,753 - 0000

SE SE SE SE, SEC. 21, T 33 S, R 34 W/E

330 feet from W/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6378

Lease Name Nix Well # 1-21

Operator: Hawkins Oil & Gas, Inc.

County Seward

Name & Address 400 S. Boston, Suite 800

Well Total Depth 6450 209.63 feet

Tulsa, OK 74103

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1650

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor J. B. Bohannon Drilling License Number 5879

Address 2324 North Highway 83, Box 6, Liberal, KS 67901

Company to plug at: Hour: 4:00 am Day: 26 Month: April Year: 19 84

Plugging proposal received from Janet McGee

(company name) Hawkins Oil & Gas (phone) 918-585-3121

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1680' with 50 sx cement

2nd plug at 840' with 25 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement. Plug water well with 5 sx cement.

Plugging Proposal Received by Steve A. Quimont
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:00 am Day: 26 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1680' with 50 sx cement, 2nd plug at 840' with

25 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rathole with 10 sx cement, 6th plug to circulate

mousehole with 10 sx cement. Plug water well with 5 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton

(if additional description is necessary, use BACK of this form. Wichita, Kansas)

(SEE/ did not) observe this plugging.

INVOICED

DATE 5-4-84

INV. NO. 1384

Signed Steve A. Quimont
(TECHNICIAN)

4-26 MAY 18 1984

RECEIVED
STATE CORPORATION COMMISSION

MAY 03 1984

CONSERVATION DIVISION
Wichita, Kansas