

To: 1 031440
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION App.
130 S. Market, Room 2078
Wichita, KS 67202

2-16

API NUMBER 15-175-21,596-0000
SE NW NW, SEC. 21, T 33 S, R 34 W/E
1050 feet from ~~NX~~ section line
1000 feet from ~~WE~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corp.
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Morlan "A" Well # 7
County Seward 112.12
Well Total Depth 6450 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1664

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382
Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: _____ Day: 15 Month: 2 Year: 1997

Plugging proposal received from John Schilling
(company name) Anadarko Petroleum Corp. (phone) 316-624-6253

were: to fill hole with heavy mud and spot cement through drill pipe

- 1st plug at Base of Chase with 100 sx cement,
- 2nd plug at 1670' with 50 sx cement, 3rd plug at 690' with 40 sx cement,
- 4th plug at 40-0' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement,
- 6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 a.m. Day: 16 Month: 2 Year: 1997

ACTUAL PLUGGING REPORT 1st plug at 3000' with 100 sx cement,
2nd plug at 1670' with 50 sx cement,
3rd plug at 690' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)
I (did / did not) observe this plugging.

INVOICED
DATE 2-25-97
INV. NO. 47658
2-16

Signed Steve Durrant
(TECHNICIAN)

RECEIVED
KANSAS CORP. COMM
FEB 24 10 35 AM '97