

1050375

15-175-20788-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C E/2 NE SE, SEC. 27, T. 33 S, R. 34 W/X  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,788-0000  
1980 feet from ~~XXX~~ SE Corner of section line  
330 feet from ~~XXX~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5469

Lease Name Schmitt "A" Well # 3

Operator: Anadarko Production Company  
Name & Address: P. O. Box 351  
Liberal, KS 67901

County Seward

Well Total Depth 6480 210.60 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1646

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Gabbert-Jones, Inc. License Number 5842

Address 830 Sutton Place, Wichita, KS 67202

Company to plug at: Hour: 4:00 am Day: 7 Month: November Year: 19 84

Plugging proposal received from John Hanna

(company name) Anadarko (phone) 316-624-6253

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2650' with 50 sx cement

2nd plug at 1690' with 40 sx cement

3rd plug at 840' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 8:00 pm Day: 7 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2650' with 50 sx cement, 2nd plug at 1690' with 40 sx cement, 3rd plug at 840' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton.

(if additional description is necessary, use BACK of this form.)

INVOICED

(check / did not) observe this plugging.

DATE 11-15-84

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 4770

11-7

RECEIVED STATE CORPORATION COMMISSION

NOV 08 1984 11-08-84 CONSERVATION DIVISION Wichita, Kansas