

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20962-00-01
Spot: E2NESW Sec/Twnshp/Rge: 27-33S-34W
1980 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: ETZOLD UNIT SOUTH Well Number: 6-2
County: SEWARD Total Vertical Depth: 6500 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

Production Casing Size: 5.5 feet: 6460 WITH 150 SX CMT
Surface Casing Size: 8.625 feet: 1654 WITH 775 SX CMT
\$211.25

Well Type: EOR UIC Docket No: E24960.10 Date/Time to Plug: 02/25/2003 11:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 6000' WITH 2 SX CMT. 50 SX CMT AT 1680'. 40 SX CMT AT 600'. 10 SX CMT AT 40'.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/25/2003 4:30 PM KCC Agent: JIM HOLLAND


Actual Plugging Report:

PERFS AT 6295-6307'. SET CIBP @ 6200' WITH 2 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG PULL OUT OF HOLE WITH CASING TO 1680' & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" TO 600'. LOAD HOLE WITH MUD & PUMP 40 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE WITH 5 1/2" TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1729' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED

DATE 3-10-03

NV NO. 2003061290



KCC WICHITA KCC Dodge City