

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20491-00-00  
Spot: CW2SWNE Sec/Twnshp/Rge: 27-33S-34W  
1980 feet from N Section Line, 660 feet from E Section Line  
Lease/Unit Name: SCHMITT - A Well Number: 1  
County: SEWARD Total Vertical Depth: 6437 feet

Operator License No.: 4549  
Op Name: ANADARKO PETROLEUM CORPORATI  
Address: 1201 LAKE ROBBINS DRIVE  
THE WOODLANDS, TX 77380

Production Casing Size: 4.5 feet: 6429 WITH 300 SX CMT  
Surface Casing Size: 8.625 feet: 1702 WITH 800 SX CMT  
\$209.20

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/05/2003 10:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 20 SX CMT FOR BOTTOM PLUG. 50 SX CMT AT 1730'. 40 SX CMT AT 600'. 10 SX CMT AT 40'.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/05/2003 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6385'. PERFS AT 6304-20'. PUMP 300# HULLS WITH 25 SX CMT TO PLUG BOTTOM. DISPLACE WITH MUD, PRESSURE TO 1000 PSIG & SHUT IN. 1ST PLUG PULL OUT OF HOLE TO 1730'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 40 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED


MAR 10 2003

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1810' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II  
(TECHNICIAN)

INVOICED

DATE 3-10-03

INV. NO. 2003061290

Form CR23