

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175 -20,737 - 0000

TECHNICIAN'S PLUGGING REPORT

C W/2 NW NE, Sec. 27, T 33 S, R 34 W/E
660 feet from N/S section line
2310 feet from W/E section line

Operator License # 5469

Lease Name Schmitt "A" Well # 2

Operator: Anadarko Production Company
Name & Box 351
Address Liberal, KS 67901

County Seward
Well Total Depth 6495 feet 211.09
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1615

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Gabbert-Jones, Inc. License Number 5842

Address 830 Sutton Place, Wichita, KS 67202

Company to plug at: Hour: 8:30 am Day: 15 Month: March Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO John Hanna

(company name) Anadarko (phone) 316-624-6253

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1650' with 50 sx cement

2nd plug at 480' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 10 sx cement

6th plug to circulate mousehole with 10 sx cement

Signed Steve Quivint
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:00 am Day: 15 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1650' with 50 sx cement, 2nd plug at 480' with
40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to
surface with 10 sx cement, 5th & 6th plugs to circulate rathole and mousehole with
10 sx cement each.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton No. 800528

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~did~~ / did not) observe this plugging.

Signed Steve Quivint
(TECHNICIAN)

INVOICED
DATE 3-23-84
INV. NO. 0898
3-15