

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20378-00-00  
Spot: CNWSE Sec/Twnshp/Rge: 29-33S-34W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: FINCHAM D Well Number: 1  
County: SEWARD Total Vertical Depth: 6370 feet

Operator License No.: 4549 Conductor Pipe: Size \_\_\_\_\_ feet: 8 207.03  
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 1699  
Address: 17001 NORTHCHASE DRIVE Production: Size 5.5 feet: 6360  
HOUSTON, TX 77060 Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/26/2002 10:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 6200' & 2 SX CMT. 1ST PLUG AT 1730' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/26/2002 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:  
PBTD 6314'. TOC @ 5150'. PERFS AT 6253-6276'. SET CIBP @ 5900' WITH 2 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG PULL OUT OF HOLE TO 1700'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF 5 1/2" TO 600' AND PUMP 40 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40' & PUMP 10 SX CMT.

RECEIVED  
JUL 17 2002  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2221' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Jim Holland PERTIP  
(TECHNICIAN)

INVOICED JUN 28 2002

DATE 7-19-02

NO. 2003060054 AD

Form CP-2/B