

1 070011 7-5  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 175-21,635 - 0000  
90' N of C  
NW NW SW, SEC. 34, T 33 S, R 34 WEX  
2400 feet from S section line  
330 feet from WX section line  
Lease Name Crow "A" Well # 3  
County Seward 211.25  
Well Total Depth 6500 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1685

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address: P.O. Box 351  
Liberal, KS 67905-0351

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382  
Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: \_\_\_\_\_ Day: 5 Month: 7 Year: 19 97

Plugging proposal received from Steve  
(company name) Anadarko Petroleum Corp. (phone) 316-624-6253

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1610'  
1st plug at 2980' with 100 sx cement, 2nd plug at 1710' with 50 sx cement,  
3rd plug at 710' with 50 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Scott Alberg (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7 p.m. Day: 5 Month: 7 Year: 1997

ACTUAL PLUGGING REPORT 1st plug at 2980' with 100 sx cement,  
2nd plug at 1710' with 50 sx cement,  
3rd plug at 710' with 50 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

I (XXX / did not) observe this plugging.

INVOICED  
DATE 7-14-97  
INV. NO. 48538  
7-5-97

Signed \_\_\_\_\_ (TECHNICIAN)

RECEIVED  
KANSAS CORP COM  
MAY 21 10 41:28