

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-20,700 ✓ 0000

C-SW $\frac{1}{2}$ , SEC. 35, T. 33 S, R. 34 W ~~XX~~

1320 FEET FROM ~~XX~~/S SECTION LINE

1320 FEET FROM ~~XX~~ SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 6120

LEASE NAME COOK WELL # 2-35

OPERATOR: Cabot Petroleum Corp.  
NAME & P.O. Box 5001  
ADDRESS Pampa, TX 79065

COUNTY SEWARD

WELL TOTAL DEPTH 6650 \$ 216.13 FEET

CONDUCTOR PIPE: SIZE 18 FEET 80

SURFACE CASING: SIZE 8 5/8 FEET 1679

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A XX

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR Ford Tool Co. LICENSE NUMBER PENDING

ADDRESS Perryton, TX

COMPANY TO PLUG AT: HOUR: 3:45pm DAY: 29 MONTH: July YEAR: 19 83

PLUGGING PROPOSAL RECIEVED FROM Jim Keagy

(COMPANY NAME) Cabot (PHONE) \_\_\_\_\_

WERE: to use 60/40 Pozmix with 2%gel and 3% CaCl and spot the following plugs:

1st plug ● 6650 w/ 50sx-----2nd plug ● 2780 w/ 50 sx

3rd plug ● 1740 w/ 40 sx-----4th plug ● 870 w/ 40 sx.

5th plug ● 40 w/ solid bridge and 20 sx to surface. Circulated 10 sx in the rathole,  
10 sx in the mousehole and 15 sx in the cellar.

PLUGGING PROPOSAL RECEIVED BY R. Beartutton  
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL \_\_\_\_\_ PART \_\_\_\_\_ NONE XX

OPERATIONS COMPLETED: HOUR: 11:29pm DAY: 29 MONTH: July YEAR: 19 83

ACTUAL PLUGGING REPORT Plugged as proposed.

Cementing by Halliburton

REMARKS: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

AUG 15 1983

CONSERVATION DIVISION  
Wichita, Kansas

I (~~DOES~~ / DID NOT) OBSERVE THIS PLUGGING.

SIGNED R. Beartutton ✓  
(TECHNICIAN)

INVOICED

DATE 8-16-83

INV. NO. 5179-W

FORM CP-2/3  
REV. 6-83