

To: 1051741
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
2000 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,347-0000
C SW SE, SEC. 36, T 7 S, R 34 ~~W~~
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9953
Operator: Harris Oil & Gas Company
Name & Address 410 17th St., Ste. 2310
Denver, CO 80202

Lease Name Schmidt Well # 1-36
County Seward
Well Total Depth 6700 217.75 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1638

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418
Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: _____ Day: 1 Month: 11 Year: 1993
Plugging proposal received from Denise Robinson
(Company name) Allen Drilling Company (phone) 316-793-5681

Work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at Hugoton/Council Grove with 100 sx cement,
2nd plug at 1660' with 50 sx cement, 3rd plug at 700' with 40 sx cement,
4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 12:15 p.m. Day: 1 Month: 11 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 3400' with 100 sx cement,
2nd plug at 1642' with 50 sx cement,
3rd plug at 700' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

NOV 16 1993

INVOICED
(If not observed this plugging.)

CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey
(TECHNICIAN)

DATE 11-19-93
INV. NO. 39251