

To: 1 090720 API NUMBER 15- 189-20,405-0000

STATE CORPORATION COMMISSION Wichita State Office Bldg. - PLUGGING SECTION App. NE NE SE, SEC. 2, T 33 S, R 38 W/E

130 S. Market, Room 2078 Wichita, KS 67202 2590 feet from S section line

TECHNICIAN'S PLUGGING REPORT 8-10 150 feet from E section line

Operator License / 4549 Lease Name Spikes C Well # 1

Operator: Anadarko Petroleum Corporation County Stevens 208.55

Name: P.O. Box 351 Well Total Depth 6417 feet

Address: Liberal, KS 67905-0351 Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1719

Abandoned Oil Well Gas Well X Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 8 a.m. Day: 9 Month: 8 Year: 19 96

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

work: 4 1/2" at 6215' w/810 sx cement, PBD 6130', Perfs at 6036-45, 6052-62', DV tool at 3145'

1st plug pump 2 sx hulls and 20 sx cement to 5836',

2nd plug run tubing to 1750' and circulate cement to surface,

Check backside.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 a.m. Day: 10 Month: 8 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement to 5836',

2nd plug ran tubing inside 4 1/2" to 1750', cemented to surface with 120 sx cement,

3rd plug pumped down 8 5/8" X 4 1/2" annulus with 10 sx cement. Pressured to 500 psi.

KANSAS CORPORATION COMMISSION

AUG 16 1996

Remarks: Used common cement by Sargent and Horton. No casing recovery-casing cemented in. (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-19-96

INV. NO. 46289

Signed [Signature] (TECHNICIAN)