

V 1 020786

7-28

API NUMBER 15-189-21,762-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE/4, SEC. 3, T 33 S, R 38 x/X
1320 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Guyer "C" Well # 1
County Stevens 55.44
Well Total Depth 1706 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 40
(one joint)

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Gabbert-Jones, Inc. License Number 5842

Address 333 E. English, Ste. 215, Wichita, KS 67202

Company to plug at: Hour: 9 p.m. Day: 28 Month: 7 Year: 19 94

Plugging proposal received from Max Deem

(company name) Gabbert-Jones, Inc. (phone) 316-263-6209

Remarks: to fill hole with heavy mud and spot cement through drill pipe Tagged out at 921'

1st plug at 1000' with 50 sx cement, 2nd plug at 600' with 50 sx cement,

3rd plug at 300' with 50 sx cement, 4th plug at 40' with 15 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:45 p.m. Day: 28 Month: 7 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 828' with 50 sx cement,

2nd plug at 600' with 50 sx cement,

3rd plug at 300' with 50 sx cement,

4th plug at 40' with 15 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 50/50 Pozmix 6% gel Class H cement by D & S.

(If additional description is necessary, use BACK of this form)

INVOICED

DATE AUG 11 1994

INV. NO. 40931

Signed Glenn R. Barlow
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
RECEIVED
KANSAS CORPORATION COMMISSION

CONSERVATION DIVISION
WICHITA, KS

7-28 SEP 27 1994