

1 090581

9-14

API NUMBER 15-189-21,779-0000

STATE CORPORATION COMMISSION

Wichita State Office Bldg. PLUGGING SECTION NE SE NW SW, SEC. 4, T. 33 S, R. 38 W&E
1744 feet from S section line
130 S. Market, Room 2078
Wichita, KS 67202
4244 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Younggren J Well # 2

Operator: Anadarko Petroleum Corporation

County Stevens

Name & Address P.O. Box 351

Well Total Depth 6300 204.75 feet

Liberal, KS 67905-0351

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1692

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Anadarko Petroleum License Number 4549

Address P.O. Box 351, Liberal, KS 67905-0351

Company to plug at: Hour: 11:30 a.m. Day: 14 Month: 9 Year: 19 95

Plugging proposal received from Jack Tuman

(company name) Anadarko Petroleum (phone) 316-554-7240

Work: 5 1/2" at 6275' w/200 sx cement, PBSD 6115', Perfs at 6020-6124', FO tool @ 3038' w/100 SX

1st plug spot cement from 6115-6000' with 35 sx.

2nd plug spot 35 sx cement at cut off,

3rd plug spot 50 sx cement at 1720',

4th plug spot 50 sx cement at 600', 4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:30 p.m. Day: 14 Month: 9 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 6000' with 2 sx hulls and 35 sx cement,

2nd plug spotted 50 sx cement at 1200',

3rd plug pulled to 800' and spotted 50 sx cement,

4th plug pulled to 40' and spotted 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

SEP 19 1995

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1200' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-21-95

INV. NO. 43555

Signed _____ (TECHNICIAN)