

To: 1020823 11-21 API NUMBER 15- 175-21,100-0000
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE SE NW NW, SEC. 23, T 33 S, R 34 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549 Lease Name Rowland A Well # 1H
Operator: Anadarko Petroleum Corporation County Seward 96.66
Name & Address P.O. Box 351 Well Total Depth 2974 feet
Liberal, KS 67905-0351 Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 660

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 9 a.m. Day: 18 Month: 11 Year: 19 94

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 2974' w/255 sx cement, PBD 2962', Perfs at 2634-46, 2664-2704, 2716-56'

1st plug pump 2 sx hulls and 25 sx cement at perfs,

2nd plug pump 3 sx hulls and 25 sx cement, 3rd plug pump 2 sx hulls and 25 sx cement,

pressure up, 4th plug pump 50 sx cement at 700', 5th plug pump 10 sx cement at 40-04'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4:30 p.m. Day: 21 Month: 11 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement at perfs on vacuum

on 11/18/94. 2nd plug on 11/21/94-pumped 3 sx hulls and 25 sx cement, then 2 sx hulls and

25 sx cement, pressured to 700#,

3rd plug pumped 50 sx cement at 700';

4th plug pumped 10 sx cement at 40 to -4'. Mud between all plugs.

Remarks: Used common cement by Sargent & Horton. Recovered 772' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (if additional description is necessary, use BACK of this form.) observe this plugging.

DATE 12-6-94

INV. NO. 41813
11-21

Signed Glenn Barlow
(TECHNICIAN)