

1 020336

11-2

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,525-0000

C SW SW, SEC. 23, T 33 S, R 34 W&E  
660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Maxwell "B" Well # 1

Operator: Anadarko Petroleum Corporation  
Name & Address P.O. Box 351  
Liberal, KS 67905-0351

County Seward 208.00

Well Total Depth 6400 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1674

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargents Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 9:30 a.m. Day: 1 Month: 11 Year: 19 90

Plugging proposal received from Doug Blair

(company name) Sargents Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 6399' w/265 sx cement, PBDT 6363', Perfs at 6234-41'

1st plug set CIBP at 6180' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 175 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 2 p.m. Day: 2 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug set CIBP at 6200' with 2 sx cement on top,

2nd plug pumped 60 sx cement at 2820', displaced with mud,

3rd plug pumped 50 sx cement at 1700', displaced with mud,

4th plug pumped 30 sx cement at 700,

5th plug pumped 10 sx cement at 40-0'.

RECEIVED STATE CORPORATION COMMISSION

NOV 8 1990

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used common cement by Sargents. Recovered 2853' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 11-19-90

INV. NO. 30003

11-2 JAN 10 1991

Signed Glenn R. Barber (TECHNICIAN)