

STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION SE SE NW NE, SEC. 34, T 34 S, R 34 XX  
130 S. Market, Room 2078  
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT  
R  
1250 feet from XXX section line  
1390 feet from E section line

Operator License # 4549 Lease Name Pottroff A Well # 1

Operator: Anadarko Petroleum Corporation County Seward 89.05

Name & Address P.O. Box 351 Well Total Depth 2740 feet

Liberal, KS 67905-0351 Conductor Pipe: Size          feet

Surface Casing: Size 8 5/8 feet 790

Abandoned Oil Well          Gas Well X Input Well          SWD Well          O&A         

Other well as hereinafter indicated         

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10:30 a.m. Day: 27 Month: 2 Year: 1997

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 4 1/2" at 2739' w/100:sx cement-TOC @ 2200', PBD 2680', Perfs at 2614-26'

1st plug pump 20 sx cement and 200 lbs. hulls on bottom,

2nd plug at 1765' with 40 sx cement,

3rd plug at 820' with 40 sx cement,

4th plug at 40' with 10 sx cement.

         Plugging Proposal Received by Kevin Strube  
         (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part          None         

Operations Completed: Hour: 10 a.m. Day: 28 Month: 2 Year: 1997

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 20 sx cement, displaced with mud,

2nd plug pulled to 1772' and pumped 40 sx cement, displaced with mud,

Pipe stuck. Reshot at 1203'.

3rd plug pulled to 820' and pumped 40 sx cement and displaced with mud.

2/28/97 Pulled to 40' and spotted 10 sx cement.

Part witnessed by Kevin Strube.

Remarks: Used common cement by Sargent & Horton. Recovered 1203' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

         observe this plugging.

**INVOICED**  
DATE MAR 11 1997  
INV. NO. 47714

Signed Dary Wenter  
         (TECHNICIAN)

KANSAS RECEIVED  
MAR 10 1997  
KANSAS CORP COMM