

1 090873

Tax: STATE-CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-175-21,672-0000

SW SE NE NW, SEC. 34, T 34 S, R 34 W/E

1250 feet from N/E section line

2300 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Matkin A Well # 2

Operator: Anadarko Petroleum Corp.

County Seward 263.25

Name: P.O. Box 351

Well Total Depth 8100 feet

Address: Liberal, KS 67905-0351

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1620

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382

Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: \_\_\_\_\_ Day: 30 Month: 10 Year: 19 97

Plugging proposal received from Jim Barlow

(company name) Anadarko Petroleum Corp. (phone) 316-624-6253

Work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3100' with 100 sx cement, 2nd plug at 1650' with 50 sx cement,

3rd plug at 650' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:30 a.m. Day: 30 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 3100' with 100 sx cement,

2nd plug at 1650' with 50 sx cement,

3rd plug at 650' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACX of this form.)

(XXX added) observe this plugging.

DATE NOV 07 1997

INV. NO. 49466

Signed \_\_\_\_\_ (TECHNICIAN)

RECEIVED  
KANSAS CORP. COM.  
1997 NOV 6 11:56