

1020132

4-5-88

4/5

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,385-R0001
SE SW, SEC. 32, T 34 S, R 34 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9783
Operator: Santa Fe Minerals, Inc.
Name & Address 13455 Noel Road, Suite 1100
Dallas, TX 75240-6620

Lease Name Dowdy Well # 23-357
County Seward 217.95
Well Total Depth 6706 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1455

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Jerry Dunkin, Inc. License Number 8733
Address P.O. Box 389, Enid, OK 73702

Company to plug at: Hour: 11 p.m. Day: 5 Month: 4 Year: 19 88

Plugging proposal received from Haines
(company name) Jerry Dunkin, Inc. (phone) 405-237-6152

were: 4 1/2" at 6625' PBDT 6280' Perfs at 2646-52, 2722-34'

- 1st plug run retrievable retainer and squeeze Chase perfs with 100 sx cement,
- 2nd plug pump 40 sx cement at 1485-1385',
- 3rd plug pump 40 sx cement at 600-500',
- 4th plug pump 10 sx cement at 36-0'.

Plugging Proposal Received by Steve Pfeifer & Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 5 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug ran retrievable retainer and squeezed Chase group with
100 sx cement at 2487', 1500 psi.,
2nd plug pumped 40 sx cement at 1485-1385',
3rd plug pumped 40 sx cement at 600-500',
4th plug pumped 10 sx cement at 36-0'.

Remarks: Recovered 2048' of 4 1/2" casing. Used Class H cement by Jerry Dunkin, Inc.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-21-88

INV. NO. 20395
4-5

AUG 3 1988

Signed Glenn R Barlow
(TECHNICIAN)