

To: 1 100047
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 189-20,457 ~~0000~~
NE SW SW, SEC. 23, T 34 S, R 35 W/E
990 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7123
Operator: H I Inc.
Name: P.O. Box 2526
Address: Liberal, KS 67905-2526

Lease Name H. Elerding Well # 1
County Stevens
Well Total Depth 6670 216.77 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1672

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 9:30 a.m. Day: 21 Month: 5 Year: 19 96

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

Work: 4 1/2" at 6587' w/250 sx cement, Perfs at 6436-60'
1st plug pump 200 lbs. hulls and 20 sx cement to bottom,
2nd plug at 3000' with 100 sx cement, 3rd plug at 1700' with 50 sx cement,
4th plug at 600' with 40 sx cement,
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 p.m. Day: 21 Month: 5 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug spotted 200 lbs. hulls and 20 sx cement to 6300',
2nd plug spotted 80 sx cement at 2800',
3rd plug spotted 50 sx cement at 1700',
4th plug spotted 40 sx cement at 600',
5th plug spotted 10 sx cement at 40' to surface.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 03 1996

CONSERVATION DIVISION
WICHITA, KS

Remarks: Used common cement by Sargent's. Recovered 3650' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOLCED

DATE: 6-10-96
INV. NO. 45761

Signed Gary Rintus
(TECHNICIAN)