

To: 1 100130
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-189-20,772-0000

5-15 E/2 NW NE, SEC. 22, T 34 S, R 35 ~~W~~
4620 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Bonsall A Well # 2

Operator: OXY USA Inc.

County Stevens 223.47

Name & Address P.O. Box 300.

Well Total Depth 6876 feet

Tulsa, OK 74102

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1773

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Gibson Well Service License Number 5866

Address Liberal, KS

Company to plug at: Hour: 11 a.m. Day: 15 Month: 5 Year: 19 97

Plugging proposal received from Reid Wilson

(company name) Halliburton (phone) 316-629-3578

Logs: 5 1/2" at 6875' w/200 sx cement, PBTD 6811', Perfs at 6740-50', CIBP at 6720'

1st plug set CIBP at 6190' with 2 sx cement on top,

2nd plug perforate at 3200' and spot 200 sx cement,

3rd plug spot 50 sx cement at 1796', displace with gel, 4th plug spot 40 sx cement at 633',

5th plug spot 10 sx cement at 40-0'.

Plugging Proposal Received by Gary Winters
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 7:22 p.m. Day: 15 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 6190' and dump 2 sx cement on top,

2nd plug perforated at 3200-3205' and spotted 200 sx cement,

3rd plug spotted 50 sx cement at 1796', displaced with gel,

4th plug spotted 40 sx cement at 633' and displaced with gel,

5th plug spotted 10 sx cement at 40-0'.

Remarks: Used HalliLite with 3% cc cement by Halliburton. Recovered 1887' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did ~~not~~) observe this plugging.

Signed Gary Winters
(TECHNICIAN)

DATE 5-22-97

INV. NO. 48162

RECEIVED
KANSAS CORP COMM
MAY 21 2:11

INVOICED

5-15