

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 1517520375 ²⁰⁰⁰

LEASE NAME FINCHAM

WELL NUMBER A-4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 29 TWP. 33 RGE 34 (X) or (W)

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

COUNTY SEWARD

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

Date Well Completed 12-7-78

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Plugging Commenced 3-1-03

Character of Well OIL

Plugging Completed 3-6-03

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-20-03 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation CHESTER Depth to Top 6235 Bottom 6254 T.D. 6530

Show depth and thickness of all water, oil and gas formations.

RECEIVED
JUN 16 2003
KCC WICHITA

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHESTER	OIL	6235	6254	8-5/8	1689	0
				5-1/2	6328	1721

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. PLUG PERFS FROM 6235 TO 6035 WITH 400# HULLS AND 25 SXS CMT. SHOT OFF 5-1/2 CSG AT 1721. SPOT 50 SXS CMT FROM 1680 TO 1530. SPOT 40 SXS CMT FROM 600 TO 480. SPOT 10 SXS CMT FROM 40 TO 3. CUT OFF AND CAP 8-5/8 3 BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151


Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.
CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101



Subscribed and sworn to before me this 11 day of June, 20 03

Lori Pearson
Notary Public

My Commission Expires: 2/26/05

ANADARKO PETROLEUM CORPORATION

PHONE 806-457-4600 • 701 S. TAYLOR ST. • SUITE 400 • AMARILLO, TEXAS 79101

ANADARKO PETROLEUM CORPORATION
A MEMBER OF THE ARCO COMPANY



June 10, 2003

Kansas Corporation Commission
Conservation Division
Finney State Office Building
130 South Market, Rm. 2078
Wichita, Kansas 67202

Attn.: Marguerite Fox

Re: Plugging Record (Form CP-4)

Fincham A-4
Sec. 29-33S-34W
Seward County, Kansas

Dear Ms. Fox:

Enclosed is the original and one copy of the Well Plugging Record (KCC Form CP-4) for the referenced well. Please file accordingly.

If additional information is required, please contact this office at the letterhead address.

Very truly yours,

Craig R. Walters, P.E.
Division Production Engineer
JTC

Enclosure

cc: Jane Jones - ALR - 20013
WI Owners
Well File
Norm Bartel - Amarillo
Justin Clark - Amarillo
Holly Frankenfield - ATL - 03091

RECEIVED
JUN 16 2003
KCC WICHITA