

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-21578 - 0000

LEASE NAME VAN AUKEN "A"

WELL NUMBER 1

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 31 TWP. 33 RGE 34 (X) or (W)

COUNTY SEWARD

Date Well Completed 11-18-96

Plugging Commenced 11-19-96

Plugging Completed 11-19-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-18-96 (date)

by STEVE MIDDLETON (KCC District Agent's Name).

Is AC0-1 filed? YES (ATTACHED) If not, is well log attached? ATTACHED

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 6600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	1686	NONE

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
11H OPEN ENDED W/DRILLPIPE TO 3000' & SET 100 SX PLUG OF 60/40 POZMIX W/6% GEL AT 3000', TOH TO 1710' & SET 50 SX PLUG AT 1710' (IN & OUT OF SURFACE PIPE), TOH TO 720' & SET 40 SX PLUG AT 720', TOH TO 40' & SET 40 SX PLUG FROM 40' TO 0', 15 SX IN RATHOLE AND 10 SX IN MOUSEHOLE. HEAVY DRILLING MUD PUMPED BETWEEN EACH PLUG. CUT OFF & CAP 8-5/8 CSG 3' BELOW GL. PERMANENTLY INSCRIBE WELL NAME, LEGAL LOCATION AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor: CHEYENNE DRILLING License No. 5382
Address P O BOX 916, GARDEN CITY, KANSAS 67846

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

DAVID W. KAPPLE (Employee of Operator) or (xxxxxxx) of above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Kapple

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 9th day of January, 1997

Freda L. Hinz
Notary Public

My Commission Expires _____

