

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-20,405

LEASE NAME SPIKES "C"

WELL NUMBER 1

2590 Ft. from S Section Line

150 Ft. from E Section Line

SEC. 2 TWP. 33S RGE 38 (X) or (W)

COUNTY STEVENS

Date Well Completed 6/15/78

Plugging Commenced 8/12/96

Plugging Completed 8/13/96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSURE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/07/96 (date)

by RICHARD LACEY (KCC District Agent's Name)

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation MORROW Depth to Top 6036' Bottom 6062' T.D. 6417'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
MORROW	GAS	6036'	6062'	8-5/8"	1719'	8-30-96
				4-1/2"	6215'	

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

P&A'D AS FOLLOWS: MIRU CSG PULLERS, MIX & SPOT 2 SXS HULLS & 20 SXS CMT TO PLUG FROM 6036' - 5836'. PULL FREE PT. CSG FREE @ 100'. PMPD 120 SXS CMT FROM 1750' - G.L. PMPD 10 SXS CMT DWN BRADENHEAD FROM 30' - 3'. CUT OFF & CAPPED 8-5/8" CSG 3' BELOW G.L. WITNESSED BY KCC REP RICHARD LACEY.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

John M. Dolan, Sr. Technical Assistant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John M. Dolan

(Address) John M. Dolan, Sr. Technical Assistant
P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 1996

FREDA L. HINZ
Notary Public - State of Kansas
My Appt. Expires 5-15-99

My Commission Expires

Notary Public