

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-21779 - 0000

LEASE NAME YOUNGGREN "J"

WELL NUMBER 2

1744 Ft. from S Section Line

4244 Ft. from E Section Line

SEC. 4 TWP. 33 RGE. 38 (E) or W

COUNTY STEVENS

Date Well Completed NOT APPLICABLE

Plugging Commenced 9-13-95

Plugging Completed 9-14-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-12-95 (date)

by STEVE MIDDLETON (KCC District Agent's Name)

Is AC0-1 filed? YES (1/95) If not, is well log attached? _____

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 6300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1692'	NONE
				5-1/2"	6278'	1994'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

TIH W/2 3/8 TUBING, TAG CMT RTNR @ 6090. CIRC W/9 PPG MUD. SPOT 35 SX CLASS H CMT. & TOH W/TBG. PULL FREE POINT, BACK OFF 5-1/2" CSG @ 1994. PULL UP & SPOT 35 SX CMT FROM 1994 TO 1884. PULL 6 JTS & SPOT 50 SX FROM 1714 TO 1564. PULL 15 JTS & SPOT 50 SX FROM 1144 TO 995. PULL TO SFC. SPOT 10 SX CMT FROM 30 FT TO SFC. CUT 8 5/8" OFF 3 FEET BELOW GL. CAP & PERMANENTLY INSCRIBE WELL NAME AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor: SARGENT & HORTON PLUGGING License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OKLAHOMA 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

DAVID W. KAPPLE (Employee of Operator) or (xxxxxxx) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Kapple

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

RECEIVED
KANSAS CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 20th day of September 1995

SEP 28 1995

L. MARG HARVEY
Notary Public - State of Kansas
My Appl. Expires 6-12-99

My Commission Expires: _____

Notary Public

CONSERVATION DIVISION
WICHITA, KS