


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sumner County. Sec. 13 Twp. 34S Rge. 1W (H) (W)
Location as "NE/CNW&SW" or footage from lines SW SW SW
Lease Owner Carl B. Anderson, Sr.
Lease Name Bacon Well No. 1
Office Address 3814 N. Santa Fe - Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dryhole
Date well completed June 17 19 56
Application for plugging filed July 16 19 56
Application for plugging approved 19
Plugging commenced June 17 19 56
Plugging completed June 18 19 56
Reason for abandonment of well or producing formation Dryhole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. T. Buffington
Producing formation None Depth to top Bottom Total Depth of Well 3997 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand	water	765	820	8 5/8"	213'	None
Sand	water	2818	2900			
Sand	water	3185	3270			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

This well was drilled to 3997 and completed on June 17, 1956, since this was Sunday we secured permission and instructions from Mr. W. T. Buffington. We placed a cement plug of 15 sacks in the bottom of the surface casing, filled casing with mud and placed a 10 sack plug in the top of the surface casing.

The locations of these cement plugs are as follows, from surface to 37 feet and another from 158' to 213' both inside the surface casing.

ED
ON COMMISSION

JUL 18 1956

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.

Raymond Price

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

Raymond Price, Jr.
3814 N. Santa Fe - OKLA City
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of July, 19 56

Pauline Lewis
Notary Public.

My commission expires 1-11-60



WELL LOG

BACON No. 1 located in the
SW SW SW Section 13 Twp 34W
Range 1W, Sumner County, Kansas.

Operator: CARL B. ANDERSON

Contractor: Moore Drilling Company

Drilling Started: May 28, 1956

Drilling Completed: June 17, 1956

FORMATIONS

Surface clay	0	42
Shale & shells	42	140
Shale	140	292
Shale & lime shells	292	497
Shale	497	711
Water sands	711	911
Shale & shells	911	1071
Shale	1071	1128
Shale & shells	1128	1316
Shale	1316	1670
Shale & lime shells	1670	2009
Lime	2009	2289
Shale with lime streaks	2289	2725
Limey sand	2725	2900
Shale	2900	3133
Water sand	3133	3347
Limey sand	3347	3475
Shale	3475	3545
Limey sand	3545	3695
Limey shale	3695	3903
Shaley sand	3903	3997

Casing Record

213' 8 5/8" 32# surface casing cemented with 200 sacks posmix.

AFFIDAVIT

I, the undersigned, being first duly sworn upon oath, state that this well log is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

CARL B. ANDERSON

By Raymond Lauer

Subscribed and sworn to before me this 17th day of July, 1956

My Commission Expires:
January 11, 1960

Pauline Lewis
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1956

CONSERVATION DIVISION
Wichita, Kansas

