


15-191-20208-0000 *JP*

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Sumner County, Sec. 19 Twp. 34S Rge. (E) 1 (W)
Location as "NE/CNW/SW" or footage from lines C SE NW
Lease Owner MacKellar Oil Co.
Lease Name Johnson Well No. 1
Office Address Suite 440 - 3545 N.W. 58th St. Ok. City, Ok.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 29, 19 70
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced May 29, 19 70
Plugging completed May 29, 19 70
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Howard Hess of Winfield
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4657 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	249'	8-5/8"	249'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from Total Depth to 250 Feet,
1/2 sax Hulls, Plug & 30 sax Cement; Heavy
Mud to 40 Feet, 1/2 sax Hulls, Plug Bridged
w/Kelly & 8 sax Cement to Base of Cellar;
2 sax Cement in Rat Hole.
Job Completed @ 6:45 P.M. on 5/29/70.


RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.
T. M. McCaul, Jr. of Sage Drilling ~~employee of owner~~ (owner or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) *T. M. McCaul Jr.*
500 Bitting Building, Wichita, Kansas
(Address)



SUBSCRIBED AND SWORN TO before me this 1st day of June, 1970
November 26, 1970

Louise K. Whitted
Louise K. Whitted - Notary Public.

RP

DRILLERS LOG

JOHNSON NO. 1

CASING RECORD:	OPERATOR:	MacKellar Oil Co.	DESCRIPTION:
8-5/8" @ 249' w/225 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	C SE NW Sec. 19-34S-1W Sumner Co., Kansas
TOTAL DEPTH:	COMMENCED:	May 14, 1970	ELEVATION: 1172 KB
4657'	COMPLETED:	May 29, 1970	


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Red Bed, & Blue Shale	0	252	
Lime & Shale	252	347	
Shale & Lime	347	810	
Lime & Shale	810	2685	
Lime, Shale, & Sand	2685	2825	
Sand, Lime, & Shale	2825	2995	
Lime, Shale, & Sand	2995	3158	
Lime & Shale	3158	3287	
Lime, Shale & Sand	3287	3425	
Sand, Shale, & Lime	3425	3512	
Lime	3512	3563	
Shale & Lime	3563	3763	
Lime & Shale	3763	4070	
Lime	4070	4145	
Lime, Shale & Chert	4145	4200	
Lime & Shale	4200	4237	
Chatt & Lime	4237	4280	
Lime & Chert	4280	4290	
Lime	4290	4360	
Lime, Chert & Shale	4360	4418	
Lime	4418	4464	
Lime & Chert	4464	4500	
Chert	4500	4510	
Lime & Chert	4510	4552	
Lime, Chert & Shale	4552	4609	
Lime	4609	4626	
Sand	4626	4657	D&A

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1970
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By T. M. McCaul, Jr.
T. M. McCaul, Jr.



Subscribed and sworn to before me this 1st day of June, 1970.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.