

STATE OF KANSAS
STATE CORPORATION COMMISSION


* A M E N D E D
Original dated 12-16-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stevens County. Sec. 8 Twp. 34S Rge. 35 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
1320 FSL, 1320 FEL

Lease Owner Cities Service Company
Lease Name Barrett "A" Well No. 2
Office Address 3545 N.W. 58th St. Oklahoma City, OK 73112
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 12-4 1980
Application for plugging filed 12-16 1980
Application for plugging approved 12-16 1980
Plugging commenced 12-2 1980
Plugging completed 12-4 1980
Reason for abandonment of well or producing formation
No commercial quantities of oil were found.
If a producing well is abandoned, date of last production
N.A. 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 6710'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1763'	0'
				5-1/2"	6560'	3388'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.* 10-10-80: Set bridge plug at 6410'

12-4-80: Dumped 1 sack cement to 6400'
Spotted cement plugs as follows:
50 sx 1637' - 1797'
25 sx 734' - 804'
15 sx 5' - 40'

Cut off casing 4' below ground level and
welded on steel cap with name and date.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Toland & Johnston

STATE OF Oklahoma COUNTY OF Oklahoma, ss.
W. A. Givens (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God

(Signature) W. A. Givens W. A. Givens
Engineering Mgr.
3545 N.W. 58th St. Oklahoma City, OK 73112
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of December, 1980

Joyce D. Porter
Notary Public.

My commission expires 6-10-84

RECEIVED
STATE CORPORATION COMMISSION

JAN 9 1981

CONSERVATION DIVISION
Wichita, Kansas