

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

SEP 17 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-191-01342-00-60

Operator's Full Name Raymond Oil Company

Complete Address 200 N Douglas, Wichita, Kan 67202

Lease Name Long Well No. 2

Location 100 N NE SE SW Sec. 12 Twp. 30 Rge. 1 (W)

County Sumner Total Depth 3842

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Woth Casing Pulling

Address 715 S A Arkansas City Mo. 67005 License No.

Operation Completed: Hour 11:45 AM Day 16 Month 9 Year 1975

The above well was plugged as follows: 254' - 8 5/8" 5 1/2" 3842'

Top perforation in 5 1/2" casing was at 3492'. Could
get down only to 3450', set plug at that point
perforation in 10' Chat. we dumped 5 sacks cement.
After recovering 2400' 5 1/2" casing pushed plug
to 240', put in 80' rock bridge and 4 yards sandy
mix cement jelled into collar.

I hereby certify that the above well was plugged as herein stated.

Signed: Tommy Gorden
Well Plugging Supervisor

INVOICED
DATE 9-17-75
INV. NO. 9091-E