

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Brown of Shamrock has this

date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.

Operator's full Name: Diamond Shamrock Corp.

Complete Address: Box 631, Amarillo, Texas

Lease Name: Klob Well No. 2

Location: C SW NE SE Sec. 33 Twp. 33 Rge. 29 <sup>26</sup>(E)(W)

County: Meade Total Depth 5862' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Brown was instructed to plug the well as follows:

9 5/8" to 1550' circulated w/ cement. 5 1/2" to 5836' cemented.

Top perforations 5785' Plug bottom w/ 25 sacks cement.

Top of cement 5400' Mud 5400' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent