

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

6-19-82

RECEIVED
STATE CORPORATION COMMISSION

JUN 22 1982

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-119-20564

Dear Sir:

Mr. Mike Godfrey of Baines & Williams Oil Co. has this date requested permission to plug the following described well:

Operator's Full Name: Gulf Oil Exploration & Production Oil Co.

Complete Address: P.O. Box 12116, Oklahoma City, Okla. 73157

Lease Name: Theis Well No. C-21

Location: 2160' FSL-330 FWL Sec. 7 Twp. 34 Rge. 26 (E) (M)

County: Meade Total Depth: 6000'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: ..

Mr. Mike Godfrey was instructed to plug the well as follows:

The cement circulated 1302' of 8 5/8" surface casing. 1st plug at 1320' with 60 sbs of cement. 2nd plug at 300' with 50 sbs of cement. 3rd plug 40' to 0' on solid bridge with 10 sbs of cement. Then circulated 10 sbs of cement in each the rat hole & mouse hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by

Very truly yours, (over)

Paul A. Luttich
Conservation Division Agent

Halliburton Co; Mrs. Marion Schmidt gave
these order while was on another well. The cement used
was 50/50 Port 4% Gell 3% C.C.

Paul A. Luttrell

[Faint, illegible handwritten notes and scribbles covering the lower half of the page.]