

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 6 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Hackney of Ashland Oil & Refining has this date requested permission to plug the following described well:

Mr. Hackney guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Company

Complete Address: Box 18695, Oklahoma City, Oklahoma

Lease Name: Berends Well No. 1

Location: App C SW/4 Sec. 31 Twp. 34 Rge. 25 (E) (W)

County Clark Total Depth 6200' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Hackney was instructed to plug the well as follows:

8 5/8" to 709' circulated w/ cement. 4 1/2" to 6200' cemented


Top perforations 5818' Plug bottom w/ 15 sacks cement.

Top of cement 5750' Mud 5750' to 750'

Spotted 35 sacks cement 750' to 650' Mud 650' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'

Very truly yours,

  
Conservation Division Agent