

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Duncan of W.P. Carr has this

date requested permission to plug the following described well:

Mr. Duncan guarantees payment of the plugging fee.Operator's full Name: W.P. Carr & Kathol PetroleumComplete Address: 900 Sutton Place, Wichita, KansasLease Name: Cox Well No. 1Location: C SE SW Sec. 24 Twp. 34 Rge. 25 ~~(E)~~ (W)County: Clark Total Depth 5800' Oil Well Gas Well Input Well SWD Well D & A Lost Hole Mr. Duncan was instructed to plug the well as follows:8 5/8" to 1243' circulated w/ cement. 5 1/2" to 5800' cemented.Top perforations 5312' Plug bottom w/ 25 sacks cement.Top of cement 5100' Mud 5100' to 1200'Spot 35 sacks cement 1200' to 1100' Mud 1100' to 45'Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent