

GP

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION

JUN 12 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Luck of Thomas & Brewer has this
 date requested permission to plug the following described well:

Mr. Luck guarantees payment of the plugging fee.

Operator's full Name: Thomas & Brewer

Complete Address: Drawer 1177 Liberal, Kansas

Lease Name: Adams Well No. # 2-5

Location: SE NW Sec. 5 Twp. 34S Rge. (E) (W) 29

County Meade Total Depth 6000' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Luck was instructed to plug the well as follows:

8 5/8"-1484' Circulated w/cement. 4 1/2"-5960' Cemented.

Top Perforations 5853'. Plug bottom w/25 Sax. cement top cement 5700'

Mud 5700' to 700' Spotted 35 Sax. cement 700' to 600'

Mud 600' to 45' Plug, Hulls, 15 Sax. cement 45' to 0

Very truly yours,

[Signature]
 Conservation Division Agent