

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION  
 (Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 19 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Casey of Diamond Shamrock has this

date requested permission to plug the following described well:

Mr. Casey guarantees payment of the plugging fee.

Operator's full Name: Diamond Shamrock Corporation

Complete Address: Box 631, Amarillo, Texas

Lease Name: Irvin Vogt "B" Well No. 1

Location: NE NE NE Sec. 4 Twp. 34 Rge. 29 (E) (W)

County: Meade Total Depth 5878' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Casey was instructed to plug the well as follows:

9 5/8" to 1540' circulated w/ cement. 5 1/2" to 5878' cemented.

Top perforations 5790' Plug bottom w/ 20 sacks cement

Top of cement 5240' Mud 5240' to 900'

Spotted 40 sacks cement 900' to 800' Mud 800' to 40'

Plug, Halls & 10 sacks cement 40' to 0'.

~~INVOICED~~

Very truly yours,

DATE \_\_\_\_\_  
 INV. NO. \_\_\_\_\_

*Edgar G. Evers*  
 Conservation Division Agent